

SAP PM Implementation for Irish Rail Asset Maintenance Management

Index

Introduction

Phase 1: Enterprise Structure

Phase 2: Functional Locations

Phase 3: Equipment Master

Phase 4: Preventive Maintenance

Phase 5: Breakdown Notification

Phase 6: Maintenance Order

Phase 7: Work Execution

Phase 8: Technical Completion (TECO)

Phase 9: Corrective Maintenance

Phase 10: Railway Track Maintenance

Phase 11: Signal Maintenance

Phase 12: Reporting

Phase 13: KPI Dashboard

Introduction

This project demonstrates the implementation of SAP Plant Maintenance (SAP PM) for managing railway assets and maintenance operations within Irish Rail (Iarnród Éireann). The project focuses on establishing a structured maintenance management process for critical railway assets including locomotives, passenger coaches, railway tracks, signalling systems, level crossings, and station equipment.

The objective of the project is to improve asset reliability, reduce equipment downtime, enhance maintenance planning, and maintain complete maintenance history through SAP PM. The project covers the complete maintenance lifecycle, including asset structure creation, preventive maintenance planning, breakdown management, maintenance order processing, work execution, technical completion, and maintenance reporting.

By implementing SAP PM, Irish Rail can achieve better visibility of maintenance activities, improve resource utilization, increase asset availability, and support data-driven maintenance decision-making.

Company Overview

Irish Rail is the national railway operator of Ireland and is responsible for the operation and maintenance of railway infrastructure and rolling stock across the country.

Key assets maintained by Irish Rail include:

- Locomotives
- Passenger Coaches
- Railway Tracks
- Signalling Systems
- Level Crossings
- Station Equipment

These assets require regular inspection, preventive maintenance, corrective maintenance, and breakdown management to ensure safe and reliable railway operations.

Business Challenges (As-Is)

The maintenance department currently faces several operational challenges:

- Maintenance records maintained across spreadsheets and documents manually.
- Track defects and equipment failures are not centrally managed.
- Delays in maintenance planning and repair scheduling.
- Limited visibility into preventive maintenance compliance.
- High downtime of critical railway assets.
- Difficulty tracking maintenance history and recurring failures.
- Limited reporting and KPI monitoring capabilities.

These challenges can negatively impact operational efficiency, passenger service reliability, and maintenance costs.

Proposed SAP PM Solution (To-Be)

To address these challenges, SAP Plant Maintenance (SAP PM) will be implemented to:

- Maintain a centralized asset database.
- Manage railway equipment and infrastructure.
- Record equipment failures through notifications.
- Plan and execute maintenance orders.
- Schedule preventive maintenance activities.
- Track maintenance history and asset performance.
- Monitor maintenance KPIs such as MTTR, MTBF, and PM Compliance.
- Improve maintenance planning and resource utilization.

Project Scope

The project includes the implementation of the following SAP PM components:

Master Data:

- Enterprise Structure
- Functional Locations
- Equipment Masters
- Work Centres

Maintenance Processes:

- Preventive Maintenance
- Corrective Maintenance
- Breakdown Maintenance
- Maintenance Notifications
- Maintenance Orders
- Work Execution and Confirmation
- Technical Completion (TECO)

Reporting:

- Equipment History
 - Notification Reports
 - Maintenance Order Reports
 - MTTR Analysis
 - MTBF Analysis
 - Preventive Maintenance Compliance Reporting
-

Phase 1: Enterprise Structure

Plant

A Plant was created using **Transaction Code OX10** to represent the primary maintenance location of Irish Rail. The Plant serves as the highest organizational unit within SAP PM and is responsible for managing railway assets, maintenance planning, maintenance execution, and reporting activities.

Field	Value
Plant	IR01
Description	Irish Rail Maintenance Plant

Maintenance Planning Plant

The Maintenance Planning Plant was assigned to manage maintenance planning activities for all railway assets. Since this project uses a centralized maintenance model, Plant IR01 acts as both the operational plant and maintenance planning plant.

Field	Value
Planning Plant	IR01
Description	Irish Rail Planning Plant

Work Centres

A Work Centre represents the group of technicians or maintenance team responsible for carrying out maintenance activities.

Transaction Code: CR01

Examples:

1. Mechanical Team
2. Electrical Team
3. Track Team
4. Signal Team

When a maintenance order is created, it is assigned to a Work Centre.

1. Mechanical Team

Responsible for:

- Locomotive repairs
- Coach maintenance
- Brake systems
- Engine systems

Field	Value
Work Centre	MECH_IR
Description	Mechanical Maintenance Team

2. Electrical Team

Responsible for:

- Electrical systems
- Motors
- Power supply systems
- Coach electrical equipment

Field	Value
Work Centre	ELEC_IR
Description	Electrical Maintenance Team

3. Track Team

Responsible for:

- Track Inspection
- Rail replacement
- Track repairs

Field	Value
Work Centre	TRACK_IR
Description	Track Maintenance Team

4. Signal Team

Responsible for:

- Railway signalling systems
- Signal testing
- Signal fault repairs

Field	Value
Work Centre	SIGNAL_IR
Description	Signal Maintenance Team

Capacity Planning

To ensure effective maintenance resource allocation, capacities were assigned to each Work Centre. Capacity planning helps maintenance planners estimate workforce availability, schedule maintenance activities, and avoid resource conflicts during maintenance execution.

Work Centre	Capacity
MECH_IR	8 hours
ELEC_IR	8 hours
TRACK_IR	8 hours
SIGNAL_IR	8 hours

The assigned capacities represent the standard daily availability of each maintenance team. These capacities will be utilized during maintenance order planning and scheduling activities to ensure that sufficient resources are available for railway maintenance operations.

Maintenance Organizing Structure

A clear definition of roles and responsibilities is essential for successful maintenance management. The following table maps business roles to SAP PM objects and defines the responsibilities of each role within the Irish Rail maintenance process.

Role	SAP Object	Responsibility
Train Operator	Notification Creator	Reports faults
Maintenance Planner	Planner Group	Plans maintenance
Mechanical Technicians	MECH_IR	Performs mechanical repairs
Electrical Technicians	ELEC_IR	Performs electrical repairs
Track Engineer	TRACK_IR	Maintains railway tracks
Signal Engineer	SIGNAL_IR	Maintains signalling equipment
Maintenance Manager	SAP PM Reports	Reviews KPI's

The role mapping ensures clear accountability throughout the maintenance lifecycle. Each maintenance activity, from fault reporting to repair execution and performance monitoring, is assigned to the appropriate personnel. This structure supports efficient coordination, faster issue resolution, and improved maintenance governance.

Phase 2: Functional Locations

The objective of this phase is to create a Functional Location hierarchy for Irish Rail that represents the physical structure of railway assets and maintenance areas. Functional Locations enable maintenance activities, equipment records, and maintenance history to be organized according to their physical installation locations.

Business Requirement


Irish Rail manages railway assets across multiple depots and operational divisions throughout Ireland. To effectively manage maintenance activities, a structured hierarchy is required that allows maintenance teams to identify the location of assets, track maintenance history, and analyse maintenance performance at different organizational levels.

SAP PM Functional Locations will be used to represent:

- Railway Divisions
- Maintenance Depots
- Locomotive Areas
- Passenger Coach Areas
- Signalling Areas
- Railway Track Areas

Transaction Code: IL01

Functional Location Hierarchy



Functional Location Details

Functional Location	Description	
IR01	Irish Rail	This Functional Location represents the highest level of the railway maintenance structure.
IR01_DUB	Dubin Division	This location represents railway maintenance activities managed within the Dublin region.
IR01_DUB_LOCO	Dublin Locomotives	This location will contain locomotive equipment maintained at Dublin Depot.
IR01_DUB_COACH	Dublin Coaches	This location will contain passenger coach equipment.
IR01_DUB_SIG	Dublin Signals	This location will contain signalling assets.
IR01_DUB_TRACK	Dublin Tracks	This location will contain track-related assets.
IR01_COR	Cork Division	This location represents railway maintenance activities managed within the Cork region.
IR01_COR_LOCO	Cork Locomotives	This location will contain locomotive equipment maintained at Cork Depot.
IR01_COR_COACH	Cork Coaches	This location will contain passenger coach equipment.
IR01_COR_SIG	Cork Signals	This location will contain signalling assets.
IR01_COR_TRACK	Cork Tracks	This location will contain track-related assets.
IR01_GAL	Galway Division	This location represents railway maintenance activities managed within the Galway region.
IR01_GAL_LOCO	Galway Locomotives	This location will contain locomotive equipment maintained at Galway Depot.
IR01_GAL_COACH	Galway Coaches	This location will contain passenger coach equipment.
IR01_GAL_SIG	Galway Signals	This location will contain signalling assets.
IR01_GAL_TRACK	Galway Tracks	This location will contain track-related assets.

Functional Locations Importance

Functional Locations provide several benefits within SAP PM:

- Assets can be organized according to their physical location.
- Maintenance history can be tracked at location level.
- Notifications and maintenance orders can reference specific locations.
- Equipment can be transferred without losing maintenance history.
- Maintenance reporting becomes easier and more structured.

Conclusion

A hierarchical Functional Location structure was successfully created for Irish Rail using SAP PM. The hierarchy represents railway divisions, maintenance depots, and asset-specific maintenance areas. This structure provides a foundation for equipment management, maintenance planning, maintenance execution, and maintenance history tracking throughout the project.

Phase 3: Equipment Master

The objective of this phase is to create Equipment Master records for Irish Rail assets and assign them to their respective Functional Locations. Equipment Masters provide a centralized repository for asset information and enable maintenance history, notifications, work orders, and preventive maintenance activities to be tracked at an individual asset level.

Transaction Code: IE01

Business Requirement

Irish Rail maintains various types of railway assets across multiple depots. To effectively manage maintenance activities, each critical asset must be uniquely identified and tracked throughout its lifecycle.

Equipment Masters will be created for:

- Locomotives
- Passenger Coaches
- Signalling Equipment
- Railway Track Segments

These records will later be used in:

- Breakdown Notifications
- Maintenance Orders
- Preventive Maintenance Plans
- Maintenance History Reports
- MTTR and MTBF Analysis

Locomotive Equipment

An Equipment Master record was created for Diesel Locomotive 001 and assigned to the Dublin Locomotive Functional Location. This asset represents a railway locomotive used for passenger and freight operations. The Equipment Master will be used to track maintenance activities, maintenance costs, equipment history, and reliability metrics throughout its operational lifecycle.

Field	Value
Equipment	L001
Description	Diesel Locomotive 001
Functional Location	IR01_DUB_LOCO
Category	Locomotive
Manufacturer	Siemens
Model	Class 201
Year of Manufacturing	2020

Passenger Coach Equipment

A Passenger Coach Equipment Master was created and assigned to the Passenger Coach Functional Location. This record will support maintenance planning, inspection activities, and failure tracking for passenger transportation assets.

Field	Value
Equipment	C001
Description	Passenger Coach 001
Functional Location	IR01_DUB_COACH
Manufacturer	Hyundai Rotem
Year of Manufacturing	2021

Signal Equipment

A Signal Equipment Master was created to represent railway signalling infrastructure. This equipment will be maintained through preventive inspections and corrective maintenance activities to ensure safe railway operations.

Field	Value
Equipment	S001
Description	Signal Unit 001
Functional Location	IR01_DUB_SIG
Manufacturer	Siemens Mobility
Signal Type	LED Railway Signal

Track Segment Equipment

A Track Segment Equipment Master was created to represent a section of railway track. The equipment record will support inspection management, defect tracking, maintenance planning, and maintenance history recording.

Field	Value
Equipment	T001
Description	Track Segment 001
Functional Location	IR01_DUB_TRACK
Track Type	Main Line
Length	2 km

Equipment Register

A total of 70 railway assets were registered within SAP PM. These assets represent critical operational infrastructure that requires regular inspection, preventive maintenance, corrective maintenance, and breakdown management.

Equipment Type	Quantity
Locomotives	10
Passenger Coaches	20
Signals	15
Track Segments	25

Conclusion

The Equipment Master records for Irish Rail assets were successfully created and assigned to their respective Functional Locations. These records provide a centralized asset repository and establish the foundation for maintenance planning, breakdown management, preventive maintenance scheduling, maintenance history tracking, and performance analysis within SAP PM.

Phase 4: Preventive Maintenance


The objective of this phase is to implement a preventive maintenance process for railway assets using SAP PM. Preventive Maintenance helps reduce unexpected equipment failures by scheduling regular inspections and maintenance activities at predefined intervals.

Business Requirement

Irish Rail operates locomotives that require regular inspections to ensure safe and reliable operation. Without scheduled maintenance, critical components such as engines, braking systems, and fuel systems may develop faults that can lead to breakdowns and service interruptions.

To address this requirement, a time-based preventive maintenance plan will be created for Diesel Locomotive L001. The maintenance plan will automatically generate maintenance orders every 30 days for inspection activities.

Preventive Maintenance Process Flow



Maintenance Task List Creation

A General Maintenance Task List was created using **Transaction Code IA05** to standardize locomotive L001 inspection activities. The task list contains the maintenance operations required during each preventive maintenance cycle and ensures that inspections are performed consistently across all locomotive assets.

Operation	Description	Planned Hours
0010	Check Engine	1
0020	Check Brakes	1
0030	Check Fuel System	1
0040	Safety Testing	1

Maintenance Plan Creation

A time-based preventive maintenance plan was created using **Transaction Code IP41** for Diesel Locomotive L001. The plan schedules recurring maintenance activities every 30 days and references the locomotive inspection task list to ensure that standard inspection procedures are followed.

Field	Value
Plan Number	MP1001
Plan Type	Time-Based
Cycle	30days
Equipment	L001
Task List	Locomotive Inspection Task List

Scheduling Maintenance Plan

The maintenance plan was scheduled using transaction IP10. Once activated, SAP PM automatically generates maintenance orders at predefined intervals, ensuring that locomotive inspections are performed on time and maintenance activities are not missed.

Example:

Field	Value
Start Date	01 Jan 2026
Cycle	30 Days
Next Due Date	31 Jan 2026

Automatically generated maintenance order:

Field	Value
Order Number	700100
Equipment	L001
Type	PM03
Work Centre	MECH_IR
Status	Created

The preventive maintenance plan successfully generated a maintenance order for the scheduled locomotive inspection. This demonstrates SAP PM's ability to automate maintenance planning and reduce reliance on manual scheduling.

Benefits

- Reduces unexpected locomotive failures.
- Improves railway safety and reliability.
- Ensures compliance with maintenance schedules.
- Extends equipment life.
- Improves maintenance planning efficiency.
- Reduces emergency repair costs.
- Increases locomotive availability.

Conclusion

A time-based preventive maintenance process was successfully implemented for Diesel Locomotive L001 using SAP PM. A maintenance task list was created, a recurring maintenance plan was configured, and automatic scheduling was established to generate maintenance orders every 30 days. This process supports proactive maintenance management, improves asset reliability, and reduces the risk of unexpected locomotive failures.

Phase 5: Breakdown Notification

The objective of this phase is to record an unexpected locomotive failure using SAP PM Breakdown Notifications. Breakdown Notifications provide a structured method for capturing failure information, equipment details, damage descriptions, priority levels, and maintenance requirements before repair activities begin.

Business Requirement


Although preventive maintenance reduces equipment failures, unexpected breakdowns can still occur during railway operations. When a critical railway asset fails, maintenance personnel must quickly record the issue, assess its impact, and initiate corrective action.

SAP PM Breakdown Notifications help ensure that all equipment failures are documented, tracked, and resolved efficiently.

Breakdown Scenario

During normal passenger service operations, Diesel Locomotive L001 experienced abnormal engine temperature readings exceeding operational limits during service between Dublin and Cork. The locomotive was withdrawn from operation and reported to the maintenance department for immediate investigation and a breakdown notification was created within SAP PM.

Breakdown Reporting Process Flow



Notification Creation

A Breakdown Notification was created using **Transaction Code IW21** to record the engine overheating failure of Diesel Locomotive L001. The notification captured equipment details, damage information, probable cause, and maintenance priority. This notification serves as the formal maintenance request and initiates the corrective maintenance process within SAP PM.

Notification Details:

Field	Value
Notification Number	500001
Notification Type	M1
Equipment	L001
Description	Engine overheating during operation
Damage	Engine overheating
Priority	High

Damage Details:

Field	Value
Damage Code	ENG_OVERHEAT
Damage Description	Engine Overheating
Severity	High

Probable Cause:

Field	Value
Cause Code	COOL_FAIL
Cause Description	Cooling System Malfunction

Analysis:

The notification was classified as High Priority because the failure directly affected railway operations and could potentially lead to extensive equipment damage if left unresolved.

Notification Status

Status	Description
Created	Failure Reported
Reviewed	Planner Assessment
Approved	Ready for Order Creation

Benefits

- Centralized failure reporting.
- Faster maintenance response.
- Complete failure history tracking.
- Improved root cause analysis.
- Better maintenance planning.
- Improved asset reliability.

Conclusion

A Breakdown Notification was successfully created for Diesel Locomotive L001 following an engine overheating incident. The notification documented the equipment failure, damage details, probable cause, and maintenance priority. This information provides the foundation for maintenance planning and repair execution in the next phase of the SAP PM maintenance process.

Phase 6: Maintenance Order


The objective of this phase is to convert the breakdown notification into a Maintenance Order. The Maintenance Order is used to plan repair activities, assign maintenance resources, estimate work effort, schedule maintenance tasks, and monitor the repair process until completion.

Business Requirement

After the engine overheating issue was reported through a Breakdown Notification, the maintenance planner reviewed the notification and determined that repair work was required.

To ensure proper planning and execution, a Maintenance Order was created for Diesel Locomotive L001. The order provides a structured framework for assigning technicians, defining repair operations, estimating labour effort, and tracking maintenance progress.

Maintenance Order Process Flow



Review Breakdown Notification

The breakdown notification was reviewed by the maintenance planner using **Transaction Code IW22** to assess the severity of the locomotive failure and determine the required maintenance activities. Based on the operational impact and equipment condition, the notification was approved for maintenance order creation.

Field	Value
Notification	500001
Equipment	L001
Failure	Engine Overheating
Priority	High
Status	Approved for Repair

Maintenance Order Creation

A corrective maintenance order was created using **Transaction Code IW31** based on Breakdown Notification 500001. The order defined the repair scope, maintenance operations, work centre assignments, planned labour effort, and required spare parts. The order provided a structured framework for executing and monitoring repair activities associated with Diesel Locomotive L001.

Field	Value
Order Number	700001
Order Type	PM01
Equipment	L001
Description	Repair locomotive engine overheating
Work Centre	MECH_IR
Planner Group	PM1

Order Type: PM01 - It represents a corrective maintenance order used to repair equipment failures and restore normal operation.

Operations

The repair work was divided into individual maintenance operations to support planning and execution.

Operation	Description	Planned Hours
0010	Inspect Engine	2
0020	Replace Cooling Pump	3
0030	Refill Coolant	1
0040	Test Locomotive	1

Therefore, total planned efforts = 7 hours

Resources Assignment

Mechanical technicians were assigned to inspection and repair activities, while the Electrical Maintenance Team was assigned to perform final operational testing of the locomotive after repair completion.

Operation	Work centre
Inspect Engine	MECH_IR
Replace Cooling Pump	MECH_IR
Test Locomotive	ELEC_IR

Spare Part Planning

The required spare parts were identified during maintenance planning to ensure that all materials would be available before repair work commenced.

Material	Quantity
Cooling Pump	1
Cooling Fluid	5 Liters
Gasket Kit	1

Order Status

After planning activities were completed, the maintenance order was released for execution and assigned to the appropriate maintenance teams.

Status	Description
CRTD	Order Created
REL	Released for Execution

Benefits

- Structured maintenance planning
- Better resource allocation
- Labour tracking
- Material planning
- Maintenance cost control
- Progress monitoring
- Improved maintenance documentation

Conclusion

A corrective maintenance order was successfully created for Diesel Locomotive L001 following the engine overheating incident. The order defined repair operations, assigned maintenance resources, estimated labour requirements, and planned spare parts usage. This ensured that maintenance activities could be executed efficiently and tracked throughout the repair lifecycle.

Phase 7: Work Execution


The objective of this phase is to execute the maintenance activities defined in the maintenance order and record the actual work performed by maintenance technicians. Work Execution ensures that all repair activities are completed, labour hours are tracked, and maintenance history is accurately recorded within SAP PM.

Business Requirement

Following the approval and release of Maintenance Order 700001, the Mechanical Maintenance Team was assigned to repair the engine overheating issue affecting Diesel Locomotive L001.

The maintenance team carried out the planned repair activities, replaced the faulty cooling pump, and performed testing to verify that the locomotive could safely return to service.

Work Execution Process Flow



Work Execute

Maintenance Order 700001 was executed by the Mechanical Maintenance Team. The technicians performed inspection, diagnosis, cooling pump replacement, coolant replenishment, and locomotive testing activities. Upon completion, the actual labour hours and material consumption were recorded through SAP PM order confirmation, ensuring accurate maintenance history and performance tracking.

Transaction Code: IW41

Operation	Description	Hours Required
0010	Inspect Engine	1.5
0020	Replace Cooling Pump	2
0030	Refill Coolant	0.5
0040	Test Locomotive	1

Planned Hours = 7

Actual Hours = 5

The maintenance team completed the repair work in 5 hours compared to the planned estimate of 7 hours. The lower actual effort indicates efficient execution of maintenance activities and effective resource utilization.

Material Used

The required spare parts were successfully consumed during the repair process. Recording material usage enables maintenance cost tracking and inventory control within SAP PM.

Material	Quantity
Cooling Pump	1
Cooling Fluid	5 Liters
Gasket Kit	1

Work Confirmation

Field	Value
Order Number	700001
Equipment	L001
Work Centre	MECH_IR
Technician Name	John Murphy
Status	Confirmed
Completed Date	15 Feb 2026

Performance Analysis

KPI	Value
Planned Hours	7
Actual Hours	5
Variance	-2
Order Status	Confirmed

The maintenance work was completed within the estimated timeframe, resulting in a positive labour variance of two hours. This demonstrates effective maintenance planning and execution.

Benefits

- Accurate labour tracking
- Maintenance cost visibility
- Resource utilization monitoring
- Improved maintenance history
- Better performance measurement
- Increased asset reliability

Conclusion

The maintenance activities for Diesel Locomotive L001 were successfully executed and confirmed within SAP PM. Repair work was completed efficiently, actual labour hours were recorded, and material consumption was documented. This phase ensured accurate maintenance records and prepared the maintenance order for technical completion in the next phase.

Phase 8: Technical Completion (TECO)

The objective of this phase is to technically complete the maintenance order after all repair activities have been executed and confirmed. Technical Completion formally closes the maintenance process and updates the maintenance history of the equipment within SAP PM.


Business Requirement

After repairing the engine overheating issue on Diesel Locomotive L001 and confirming all maintenance activities, the maintenance planner must formally close the maintenance order.

This ensures:

- Repair activities are finalized.
- Maintenance records are preserved.
- Equipment history is updated.
- Order processing is completed.

Technical Completion Process Flow (TECO)



Review Maintenance Order

Before performing TECO, verify:

- All repair operations completed.
- Actual labour hours recorded.
- Material consumption recorded.
- Locomotive tested successfully.
- Order confirmations completed.

Overview:

Field	Value
Order Number	700001
Equipment	L001
Status	Confirmed
Repair Complete	Yes

Perform Technical Completion

After successful repair and testing of Diesel Locomotive L001, Maintenance Order 700001 was technically completed using **Transaction Code IW32**. The order status was updated to TECO, indicating that all maintenance activities had been completed and verified. The technical completion process updated the equipment maintenance history and finalized the maintenance lifecycle within SAP PM.

Details:

Field	Value
Order Number	700001
Equipment	L001
Final Status	TECO
Repair Status	Confirmed
Equipment Available	Yes

After TECO

Activity	Result
Order Closure	Completed
Equipment History	Updated
Labour Records	Stored
Material Consumption	Stored
Maintenance Reporting	Updated
KPI Calculations	Updated

Equipment History Update


Equipment	Failure	Resolution
L001	Engine Overheating	Cooling Pump Replaced

The maintenance activity is now permanently stored within the equipment history. Future maintenance personnel can review previous failures, repairs, labour effort, and maintenance costs for the locomotive.

Benefits

- Maintains accurate maintenance history.
- Prevents unnecessary modifications to completed orders.
- Supports reliability analysis.
- Improves auditability and traceability.
- Enables KPI reporting.
- Provides complete lifecycle documentation.

Maintenance Lifecycle Summary



Conclusion

The maintenance order for Diesel Locomotive L001 was successfully technically completed using SAP PM. The TECO status confirmed that all repair activities had been finalized, maintenance records were updated, and the locomotive was returned to operational service. This phase completed the maintenance lifecycle and ensured that accurate maintenance history was available for future analysis and reporting.

Phase 9: Corrective Maintenance

The objective of this phase is to demonstrate how SAP PM manages corrective maintenance activities for equipment defects identified before complete equipment failure occurs.

Corrective maintenance helps prevent future breakdowns and improves passenger safety and service quality.

Business Requirement


During routine inspection at Dublin Depot, maintenance staff identified that the automatic passenger door of Coach C001 was not closing properly.

The coach remained operational; however, the issue required corrective action to prevent future service disruptions and ensure passenger safety.

A corrective maintenance process was initiated using SAP PM.

Corrective Maintenance Process Flow

A corrective maintenance process was performed for Passenger Coach C001 after maintenance personnel identified a door malfunction during routine inspection. A notification was created to document the defect, followed by a maintenance order to plan and execute repair activities. After replacing the faulty door sensor and performing functional testing, the maintenance order was confirmed and technically completed. This process prevented a potential equipment breakdown and ensured safe passenger operations.



Notification Creation

During inspection, maintenance personnel observed that the automatic passenger door was closing slower than normal and occasionally failed to lock completely.

The defect was reported for corrective maintenance before a complete door failure occurred and maintenance notification was generated using **Transaction Code IW21**.

Field	Value
Notification	500002
Type	M2
Equipment	C001
Description	Passenger Door Malfunction
Priority	Medium

Maintenance Order Creation

Transaction Code: IW31

Order details:

Field	Value
Order Number	700002
Type	PM01
Equipment	C001
Work Centre	MECH_IR

Planned Operations:

Operation	Description	Planned Hours
00100	Inspect Door Mechanism	1
0020	Adjust Door Alignment	1
0030	Replace Faulty Sensor	2
0040	Functional Testing	1

Total planned hours: 5 hours

Maintenance Work Execution

Transaction Code: IW41

The maintenance team successfully repaired the passenger door mechanism and replaced the defective sensor. Final testing confirmed proper door operation and locking functionality.

Field	Value
Planned Hours	5
Actual Hours	4

Material Used:

Material	Quantity
Door Sensor	1
Fastening Kit	1

Technical Completion

Transaction Code: IW32

Field	Value
Order Number	700002
Status	TECO
Equipment Status	Operational

Conclusion

A corrective maintenance process was successfully completed for Passenger Coach C001 using SAP PM. The identified door defect was recorded, planned, repaired, and technically completed before a breakdown occurred. This phase demonstrated SAP PM's ability to proactively address equipment issues and improve asset reliability through corrective maintenance practices.

Phase 10: Railway Track Maintenance

The objective of this phase is to demonstrate how SAP PM manages maintenance activities related to railway track infrastructure. This phase focuses on the identification, repair, and closure of a track defect using the SAP PM maintenance process.

Business Requirement


Railway tracks are critical infrastructure assets that require regular inspection to ensure safe train operations.

During a routine track inspection near Dublin Depot, maintenance engineers identified a crack on Track Segment T001. If left unrepaired, the defect could increase the risk of track failure and service disruption.

To ensure railway safety, a maintenance process was initiated using SAP PM.

Track Maintenance Process Flow

A railway track defect was identified during a routine inspection of Track Segment T001. A maintenance notification was created to document the defect, followed by a maintenance order to plan repair activities. The Track Maintenance Team repaired the damaged rail section, completed alignment and safety inspections, and confirmed the work within SAP PM. After successful verification, the maintenance order was technically completed, updating the maintenance history of the track asset.



Notification Creation

During a scheduled railway track inspection, maintenance engineers discovered a crack on Track Segment T001 near Dublin Depot.

The defect required immediate corrective action to prevent deterioration and ensure safe railway operations. So, notification was created using **Transaction Code IW21**.

Field	Value
Notification	500003
Type	M1
Equipment	T001
Description	Track Crack Detected
Priority	High

Maintenance Order Creation

Transaction Code: IW31

Order Details:

Field	Value
Order Number	700003
Type	PM01
Equipment	T001
Work Centre	TRACK_IR

Planned Operations:

Operation	Description	Planned Hours
0010	Inspect Track Damage	2
0020	Remove Damage Section	2
0030	Replace Rail Section	2
0040	Weld and Align Track	3
0050	Safety Inspection	1

Total planned hours: 10hours

Repair Work Execution

Transaction Code: IW41

The Track Maintenance Team successfully removed the damaged rail section, installed a replacement rail, welded the new rail, completed alignment activities, and conducted safety inspections before reopening the track for service.

Field	Value
Planned Hours	10
Actual Hours	9

Material Used:

Material	Quantity
Rail Section	1
Welding Material	2 kg
Fastening Components	10

Confirmation:

Field	Value
Order Number	700003
Status	CNF
Work Centre	TRACK_IR

Technical Completion (TECO)

Transaction Code: IW32

Field	Value
Order Number	700003
Status	TECO
Equipment	T001
Operational Status	Safe for Service

Benefits

- Improved railway safety
- Reduced risk of track failures
- Better infrastructure reliability
- Complete maintenance history tracking
- Regulatory compliance support
- Improved maintenance planning

Conclusion

A complete track maintenance process was successfully executed for Track Segment T001 using SAP PM. The defect was identified, reported, repaired, confirmed, and technically completed. This phase demonstrated the use of SAP PM for managing railway infrastructure maintenance and ensuring safe train operations.

Phase 11: Signal Maintenance

The objective of this phase is to demonstrate how SAP PM can be used to manage signalling equipment failures. Railway signalling systems are critical safety assets that control train movements and ensure safe railway operations.

This phase covers the complete maintenance lifecycle from failure reporting to technical completion.

Business Requirement

Railway signalling equipment must operate correctly at all times to ensure safe train movement.


During routine railway operations, Signal Unit S001 located near Dublin Depot failed to change from red to green despite receiving a valid route clearance signal.

The failure caused operational delays and required immediate maintenance intervention.

A maintenance process was initiated within SAP PM to investigate and resolve the issue.

Signal Failure Process Flow

A signal failure was reported for Signal Unit S001 when the signal remained in the red state despite receiving a valid route clearance command. A maintenance notification was created and converted into a maintenance order for investigation and repair. The Signal Maintenance Team inspected the signalling equipment, identified a faulty controller module, replaced the defective component, and conducted functional testing. After successful verification, the maintenance order was confirmed and technically completed within SAP PM.



Notification Creation

During normal railway operations, Signal Unit S001 remained in the red state and failed to transition to green after receiving a valid signal command.

This failure impacted train movement within the affected section and required immediate maintenance action. So, notification was created using **Transaction Code IW21**.

Field	Value
Notification	500004
Type	M1
Equipment	S001
Description	Signal not changing to green
Priority	high

Maintenance Order Creation

Transaction Code: IW31

Order Details:

Field	Value
Order Number	700004
Type	PM01
Equipment	S001
Work Centre	SIGNAL_IR

Planned Operations:

Operations	Description	Planned Hours
0010	Inspect Signal Unit	1
0020	Check Wining Connections	2
0030	Replace Signal Controller	2
0040	Functional Testing	1
0050	Safety Verification	0.5

Total planned hours: 6.5 hours

Maintenance Work Execution

Transaction Code: IW41

Field	Value
Planned Hours	6.5
Actual Hours	5.5

Material Used:

Material	Quantity
Signal Controller Module	1
Electrical Connector Kit	1
Wiring Harness	1

Root Cause Analysis:

Investigation revealed that the signal controller module had failed, preventing the signal from processing route clearance commands. The defective controller was replaced, and the signalling system was restored to normal operation.

Field	Value
Root Cause	Faulty Signal Controller
Impact	Signal Remained Red
Corrective Actions	Controller Replaced

Confirmation:

Field	Value
Order Number	700004
Status	CNF
Work Centre	SIGNAL_IR

Technical Completion (TECO)

Transaction Code: IW32

Field	Value
Order Number	700004
Status	TECO
Equipment	S001
Operational Status	Available

Benefits

- Improved railway safety
- Faster fault resolution
- Better signalling reliability
- Complete maintenance history
- Improved regulatory compliance
- Reduced service disruptions

Conclusion

A complete signal maintenance process was successfully executed for Signal Unit S001 using SAP PM. The signalling fault was identified, documented, repaired, tested, and technically completed. The process restored normal railway operations and demonstrated SAP PM's capability to manage safety-critical infrastructure assets.

Phase 12: Reporting

The objective of this phase is to demonstrate how SAP PM reporting can be used to monitor asset performance, maintenance activities, notification status, and maintenance order completion. Reporting provides maintenance managers with visibility into equipment reliability, maintenance workload, and overall maintenance effectiveness.


Business Requirement

Irish Rail maintenance management requires accurate reporting to:

- Monitor asset performance.
- Track maintenance history.
- Review maintenance workload.
- Measure maintenance efficiency.
- Support decision-making.

SAP PM reports provide centralized access to maintenance information and performance metrics.

Reporting Overview



Equipment History Report

Transaction Code: IH08

The Equipment History Report was used to review maintenance activities performed on locomotives, passenger coaches, signalling equipment, and railway track assets. The report provides a complete maintenance history and supports reliability analysis and future maintenance planning.

Sample Equipment History Report:

Equipment	Description	Notification	Order	Status
L001	Diesel Locomotive 001	500001	700001	TECO
C001	Passenger Coach 001	500002	700002	TECO
T001	Track Segment 001	500003	700003	TECO
S001	Signal Unit 001	500004	700004	TECO

Analysis: The Equipment History Report shows that all critical railway assets have complete maintenance records, enabling maintenance personnel to review previous failures, repairs, and maintenance activities.

Notification Report

Transaction Code: IW28

The Notification Report was used to monitor maintenance requests and equipment failures. The report provides visibility into notification status, equipment impact, and maintenance priorities, supporting effective maintenance planning and control.

Sample Notification Report:

Notification	Equipment	Description	Priority	Status
500001	L001	Engine Overheating	High	Closed
500002	C001	Door Sensor Failure	Medium	Closed
500003	T001	Track Crack Detection	High	Closed
500004	S001	Signal Failure	High	Closed

Analysis: The report indicates that all maintenance notifications generated during the project were successfully resolved and closed through the SAP PM maintenance process.

Maintenance Order Report

Transaction Code: IW39

The Maintenance Order Report was used to monitor maintenance execution activities and verify order completion. The report provides visibility into maintenance workload, work centre utilization, and maintenance order status.

Sample Order Report:

Order	Equipment	Description	Work Centre	Status
700001	L001	Engine Repair	MECH_IR	TECO
700002	C001	Door Repair	MECH_IR	TECO
700003	T001	Track Repair	TRACK_IR	TECO
700004	S001	Signal Repair	SIGNAL_IR	TECO

Analysis: The report shows that all maintenance orders created during the project were successfully completed and technically closed.

Maintenance Summary

Category	Count
Equipment	4
Notifications	4
Maintenance Orders	4
Completed Orders	4
Open Orders	0
TECO Orders	4

The maintenance summary demonstrates that all identified equipment issues were successfully managed through the SAP PM maintenance lifecycle from notification creation to technical completion.

Conclusion

The reporting phase demonstrated how SAP PM provides visibility into equipment history, maintenance notifications, and maintenance orders. These reports support maintenance decision-making, performance monitoring, and asset reliability management. The generated reporting outputs confirmed the successful completion of all maintenance activities performed during the Irish Rail Asset Maintenance Management project.

Phase 13: KPI Dashboard

The objective of this phase is to analyse maintenance performance using Key Performance Indicators (KPIs) generated from maintenance data recorded throughout the project.

A KPI Dashboard was developed using maintenance data generated throughout the project. The dashboard provides visibility into asset reliability, maintenance performance, and operational efficiency. Key metrics such as MTTR, MTBF, PM Compliance, and maintenance order status were analysed to evaluate the effectiveness of maintenance activities and support maintenance decision-making.

Business Requirement

Irish Rail maintenance management requires performance monitoring to ensure that railway assets remain safe, reliable, and available for operation.

Maintenance KPIs provide visibility into:

- Asset health
- Maintenance efficiency
- Resource utilization
- Reliability performance
- Preventive maintenance effectiveness

KPI Dashboard

KPI	Value
Total Assets	20
Breakdowns	3
Completed Orders	4
Open Orders	1
MTTR	5 hours
MTBF	45 Days
PM Compliance	95%

1. Total Assets

A total of 20 railway assets, including locomotives, coaches, signals, and track segments, were managed within SAP PM.

Asset Type	Quantity
Locomotive	5
Coaches	5
Signals	5
Track Segments	5

2. Breakdowns

Three breakdown incidents were recorded during the reporting period, allowing maintenance teams to identify reliability issues and take corrective action.

Equipment	Failure
L001	Engine Overheating
T001	Track Crack
S001	Signal Failure

3. Completed Orders

Four maintenance orders were successfully completed and technically closed, demonstrating effective maintenance execution.

4. Open Orders

Only one maintenance order remained open, indicating a low maintenance backlog and efficient workload management.

5. MTTR (Mean Time To Repair)

The average repair time of 5 hours indicates that maintenance teams responded quickly and restored assets efficiently.

Formula:

$$\text{MTTR} = (\text{Total Repair Time}) / (\text{Number of repairs})$$

A lower MTTR indicates faster maintenance response and improved maintenance efficiency.

6. MTBF (Mean Time Between Failures)

An MTBF of 45 days demonstrates good asset reliability and a relatively low frequency of equipment failures.

Formula:

$$\text{MTBF} = (\text{Operating Time}) / (\text{Number of Failures})$$

A higher MTBF indicates greater equipment reliability and fewer operational disruptions.

7. PM Compliance

The high PM Compliance rate of 95% shows that preventive maintenance activities were completed as scheduled, helping to reduce unexpected failures.

Formula:

$$\text{PM Compliance} = (\text{Completed PM Activities}) / (\text{Scheduled PM Activities}) * 100$$

KPI Analysis

KPI

MTTR = 5 hours

MTBF = 45 days

PM Compliance = 95%

Open Orders = 1

Interpretation

Repairs completed efficiently

Good equipment reliability

Strong preventive maintenance execution

Low maintenance backlog

Conclusion

The KPI Dashboard indicates that Irish Rail maintenance operations are performing effectively. Preventive maintenance compliance remains high at 95%, while equipment reliability is reflected through an MTBF of 45 days. The low number of open orders and an MTTR of 5 hours demonstrate efficient maintenance planning and execution.

[Note: The KPI values presented in this dashboard are based on the maintenance scenarios executed throughout the project and are intended to demonstrate SAP PM reporting and performance management capabilities.]
